



WHITACRE GREER COMPANY

	WT.	PCS/SQ.FT.	PCS/PALLET SQ.	FT/PALLET	WT/PALLET
4 x 8 x 1-1/2	3.8	4.5	702	156	2727#
4 x 8 x 2-1/4	3.5	4.5	486	108	2733#
4 x 8 x 2-3/4	7.2	4.5	378	84	2787#
8 x 8 x 2-1/4	11.1	2.25	216	96	2463#
8 x 8 x 2-3/4	14	2.25	168	75	2417#
3-5/8 x 7-5/8 x 1-1/4 *	2.8	4.5	960	213	2753#
3-5/8 x 7-5/8 x 2-1/4 *	5.1	4.5	540	120	2819#

*** MODULAR PAVERS SET IN MORTAR WITH 3/8-INCH MORTAR JOINT**

6 x 3 x 2-1/4	3.2	8	1016	127	3311#
6 x 3 x 2-3/4	4.1	8	696	87	2913#
6 x 6 x 2-1/4	6.3	4	508	127	3260#
6 x 6 x 2 3/4	8.1	4	348	87	2880#
6 x 9 x 2 1/4	9.3	2.7	344	127	3258#
6 x 9 x 2 3/4	12.5	2.7	256	94	3260#
2 1/4 x 9 x 2 1/4 ***	3.5	7.1	800	113	2865#
2 1/4 x 9 x 3 ***	4.6	7.1	672	95	3156#
3 x 9 x 3 ***	6	5.3	512	97	3137#
MASONRY SPLITS 3 5/8 x 7 5/8 x 1 1/4 ****	2.8	N/A	780	N/A	2200#

****** MASONRY SPLITS ARE PACKAGED IN CUBES - 5 STRAPS OF 156 PIECES PER STRAP**

